

EVANS ROOFING CASE STUDY

Big Truck Tacos Restaurant

Project Location

530 NW 23, Oklahoma City,
Oklahoma 73103

Building Representative

Chris Lower, Big Truck Tacos

Project Date

March 2018

Roofing System

VersiFleece® TPO

Malarkey Highlander
Laminated shingles

Ideal for re-roofing or new construction, VersiFleece TPO incorporates all the benefits of VersiWeld reinforced TPO membrane with the additional benefits of a non-woven polyester fleece backing offering unmatched durability, puncture resistance and reflectivity.

Warranty

20 year manufacturers material warranty



The Project

This iconic Oklahoma City Uptown restaurant is a popular gathering space for OKC’s urban dwellers. The project included a flat- roof, a pitched

shingled roof and significant rooftop HVAC removal/replacement.

The Challenge

The flat-roof had been in a state of disrepair due to improper drainage, improper roof top HVAC systems curb placement and years of wind damage. Additionally, the restaurant’s Operations Manager had legitimate concerns about the staging of roofing equipment and materials within the confines of a small urban lot. Significant HVAC, and electrical work needed to be organized so all work could be completed within 4 days without shutting down restaurant operations.

The Solution

First, we conducted a pre-construction meeting between trades to ensure all trades could perform work simultaneously, utilizing the same heavy equipment. Furthermore, we designated staging areas for tools, materials and equipment.

Next, we installed an 1/8" Versico Poly-ISO tapered insulation system. We fully adhered VersiFleece 115 mil TPO utilizing Dash A & B low rise foam adhesive.

We installed custom architectural 24 gauge 4" x 4" metal edge with 22 gauge continuous cleat and covered with Versico cover tape.

Malarkey Highlander heavyweight laminated shingles were installed on the mansard roof and sloped roof sections.

